

# BRUHAT BANGALORE MAHANAGARA PALIKE

## MODIFIED SCHEDULE - B

**Name of the Work: Improvements to roads and drains at Jakkur Gramatana in ward no.07, Byatarayanapura.**

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Unit | Rates      |                                                                            |
|---------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------------|----------------------------------------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      | KRIDL      |                                                                            |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      | In Figures | In Words                                                                   |
| 1       | 157.95        | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                           | Cum  | 86.92      | Rupees Eighty Six and Ninety Two Paise Only                                |
| 2       | 12.15         | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work                                                                             | Cum  | 5338.35    | Rupees Five Thousand Three Hundred Thirty Eight and Thirty Five Paise Only |
| 3       | 8.10          | Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing etc complete as per specifications and directions of engineer in charge of the work                                                                        | Cum  | 5338.35    | Rupees Five Thousand Three Hundred Thirty Eight and Thirty Five Paise Only |
| 4       | 493.00        | Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)                                                                                                                                                                                             | Sqm  | 2100.00    | Rupees Two Thousand One Hundred Only                                       |
| 5       | 157.95        | Loading and unloading of stone boulder/stone aggregates/sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                    | Sqm  | 106.00     | Rupees One Hundred Six Only                                                |
| 6       | 171.00        | Providing and constructing load bearing wall with solid concrete solid blocks having block density not less than 18000 Kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confimring to IS 2185 (pART 1):2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materialsincluding cost of all materilas, labour charges, scaffolding, curing complete as per specifications. with solid concrete blocks 400x200x200mm etc complete as per specifications and directions of engineer in charge of the work | Cum  | 993.22     | Rupees Nine Hundred Ninety Three and Twenty Two Paise Only                 |

**EXECUTIVE ENGINEER-4**  
Signature of the Contractor  
**BENGALURU-560 010**

**Executive Engineer**  
**Byarayanapura Division**  
**BBMP, Bangalore - 92**